Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.

Schedule - B

Name of the Work :Removal of Debris & Disilting of Drains in Dasarahalli Ward No 15

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted	
				In Figures (Rs)	In Words (Rs)
1	Removing B.S. slab of drain and stacking with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	Sqm	5004	65.72	Rupees Sixty Five and Seventy Two Paisa Only
2	Excavation and removal of silt and silt mix with sand in slushy condition form canal bed including disposing of the same in spoil bank or on canal embankment in layers as directed etc., complete with an initial lead upto 50m	Cum	1206	212.6	Rupees Two Hundred and Twevel and Sixty Paisa Only
3	Refixing stone slabs of drains and pointing in CM 1:3 etc complete	Sqm	5004	80.56	Rupees Eighty and Fifty Six Paisa Only
4	J.C.B. Excavator on hire basis including JCB Operator with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work	Days	12	6720	Rupees Six Thousand Seven Hundred and Twenty Only
5	Tractor 40 HP on hire basis including Tractor Driver with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work	Days	48	1416	Rupees One Thousand Four Hundred and Sixteen Only

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bangalore

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner